

# ATMC MDU ONT Installation Layout for Multi-Family FTTP Applications

## New Construction Multifamily Dwellings: Builder / Contractor Installation Responsibility

- o Install (1) Internal Communications Distribution Panel (ICDP), 120V AC 20A circuit & receptacle, and install ONT Feed Cables [ (4) CAT5- Voice & Data Cables and (2) RG-6 CATV Cables ] to 1<sup>st</sup> floor equipment room as indicated per each Main Unit. Establish 4'x8'x3/4" backboard, 120V AC circuit, and #6 Ground Wire for equipment installation.
- o \* Items shown in blue (ONT, Fiber Cable, UPS, 12V/Data Cable, ICDP components) to be installed by ATMC.
- o \* Required items shown in red to be provided and installed by builder or contractor.

## Physical Layout View

